Kimley»Horn

September 19, 2025

Mr. Steven Marfitano, P.E.
City and County of Denver
Department of Transportation and Infrastructure
201 W. Colfax Avenue, Denver, CO 80202

**RE:** ***W Alameda Lane Reduction***
***City and County of Denver, CO***
***Master Contract Alfresco No.: 202056606***
***Task Order No. 2***
***Task Order Alfresco No.: PO-00120141***
***Amendment #4 - DRAFT***

Dear Mr. Marfitano:

**Kimley-Horn and Associates, Inc.** (the "Consultant" or "Kimley-Horn") is pleased to submit this Amendment to modify the agreement dated August 15, 2022 (the "Agreement") with the **City and County of Denver** (the "Client", "City", or "CCD") for the W Alameda Lane Reduction Project for the Department of Transportation and Infrastructure in Denver, Colorado (the "Project"). Kimley-Horn has entered into the Agreement with Client for the furnishing of professional services, and the parties now desire to amend the Agreement.

Therefore, it is mutually agreed that the Agreement is amended to include additional services for the project as set forth below. The parties ratify the terms and conditions of the Agreement not inconsistent with this Amendment, all of which are incorporated by reference.

## Project Understanding

Kimley-Horn understands that the City and County of Denver desires planning, engineering, and design services for the Alameda Avenue Lane Reduction Project. The purpose of this project is to update the previously completed analysis and final design as noted below.

- City desires update of previous analysis and final design efforts for an alternative consisting of one (1) westbound through travel lane, one (1) turn lane/median, and two (2) eastbound through travel lanes.
- Existing traffic signals within the project limits other than the intersection of Alameda Ave & Emerson St are to remain as-is with minor modifications to signal equipment as part of the project improvements. No traffic signal structure improvements are planned or included for these intersections. Add Alternate Task 7 includes scope for the modification of the traffic signal at Alameda Ave & Emerson St.
- Intersection improvements at Alameda Ave & Franklin St included in 2021 Pedestrian Program Intersection Improvements PRJ-10002820/310/50/501100 dated 7/18/2022 prepared by Muller Engineering Company are to be designed and constructed by others and will be reflected as existing conditions in the Alameda Lane Reduction final design plans.
- City desires a revised approach to the traffic analysis, safety analysis, final design, and public engagement tasks as noted in the scope of services below.

# Scope of Services

## REVISED TASK 1 PROJECT MANAGEMENT AND MEETINGS

Kimley-Horn will provide project management and administrative services and coordinate, prepare for, and attend meetings with DOTI, key stakeholders, and subconsultants as detailed below.

### Kickoff Meeting

Kimley-Horn will prepare for, coordinate, and attend up to one (1) Kickoff Meeting. This meeting is anticipated to include the consultant, subconsultants, and DOTI staff.

### Coordination Meetings

Kimley-Horn will prepare for, coordinate, and attend up to nine (9) one-hour check-in virtual meetings with the DOTI Project Manager and staff. The purpose of these meetings will be to review project status and coordinate on action items.

### Stakeholder Meetings

Kimley-Horn will prepare for, coordinate, and attend up to two (2) one-hour check-in virtual meetings with City and/or public stakeholders.

### Project Oversight/Management

The Kimley-Horn project manager will provide weekly oversight and management, invoicing, and other project management services. It is assumed that up to thirty-six (36) hours of effort will be provided for this task based on an assumed up to nine (9) month project schedule.

## REVISED TASK 2 DATA COLLECTION

### Traffic Counts

Kimley-Horn, through use of a well-qualified subconsultant will collect traffic data along the corridor. Peak hour turning movement counts (AM and PM) will be collected at up to one (1) intersection identified below:

- Virginia Ave & Downing St.

Additionally, 24-hour average daily (ADT) traffic counts with vehicle classifications and speeds will be collected at up to three (3) locations along the corridor identified below:

- Alameda Ave between S Lincoln St and S Logan St;
- Alameda Ave between S Logan St and S Downing St; and
- Alameda Ave between S Downing St and S Franklin St.

### Crash Data

Kimley-Horn will gather recent crash reports provided by DOTI for the most recent 3-years.

*(The remainder of this page intentionally left blank)*

DRAFT

## REVISED TASK 3 TRAFFIC AND SAFETY ANALYSIS AND EVALUATION

**Traffic Analysis**

Kimley-Horn will utilize the previously developed model without any re-calibration to re-evaluate the alternative identified in the Project Understanding. The analysis will consider and confirm anticipated traffic diversion, queuing, delay, and impacts on the project corridor, project intersections, and adjacent facilities. Additionally, individual intersection spot treatments and interventions will be analyzed to ensure recommendations are consistent with crash and traffic conditions.

Kimley-Horn will recommend corridor traffic signal timing and develop a proposed signal timing plan that can be implemented during construction. Field observation and verification of timing will be completed upon implementation.

For Virginia Ave & Downing St, Kimley-Horn will provide an evaluation and recommendations based on existing and proposed intersection conditions. Improvements may include:

- Implementing protected-only southbound left and northbound left-turns;
- Prohibiting right-turn on red for all approaches;
- Installing paint-and-post pedestrian bulb-outs on the east and west legs of the intersection;
- Adding new backplates on signal heads; and
- Reviewing Virginia Ave speed limits.

### Crash and Safety Analysis

Kimley-Horn will complete a crash and safety analysis for the corridor and at each intersection. This analysis is anticipated to consist of a review of crash patterns, crash reduction factors (CRFs), and validation the draft DOTI analysis completed. The summary will include specific mitigations for identified crash patterns and confirm individual intersection treatments and interventions. These intersection treatments and interventions will be summarized in a memorandum format, providing justification for each component of the final project and outlining the anticipated impacts.

## REVISED TASK 5 PUBLIC ENGAGEMENT

Kimley-Horn will provided public engagement support for the project. It is understood that engagement efforts will be led by the City Community Designers with minimal support from Kimley-Horn and that a Public Meeting is not anticipated or included in the scope of work. Kimley-Horn will provide information for with content revisions for website and previously prepared print materials. Spanish translation will be provided for engagement materials.

## REVISED TASK 6 FINAL DESIGN

Kimley-Horn will complete final design and plan development services for the project improvements based on the previously prepared final design plans, the anticipated improvements noted in the Project Understanding, and analysis completed in Revised Task 3. Kimley-Horn will endeavor to utilize previously completed design and plan development effort to the extent possible for all revised final design efforts. Design and plan development for the Virginia Ave & Downing St intersection are new scope for Amendment #4. Signal improvements included in this task consist of minor signing and traffic signal modifications. Traffic signal modifications including pole relocations are not included in the base scope, but are included in Add Alternate Task 7 – Traffic Signal Modifications.

DRAFT

Final design plans and deliverables are anticipated to consist of the following:

- Cover Sheet (up to one [1] sheet);
- General Notes (up to four [4] sheets);
- CCD Standard Details (up to one [1] sheet);
- Summary of Approximate Quantities (up to one [1] sheet);
- Tabulations (up to one [1] sheet);
- Signing and Striping Removal Plan (up to six [6] sheets);
- Signing and Striping Plan (up to seven [7] sheets);
- Virginia Ave & Downing St Intersection Improvement Plans (up to one [1] sheet);
- Details (up to four [4] sheet);
- Revised Engineer's Opinion of Probable Construction Costs (EOPCC); and
- Revised Specifications.

Kimley-Horn will submit Plans, Specifications, and Estimates (PS&E) at a 60% level. Kimley-Horn will address up to one (1) round of reasonable, consolidated City ER comments on the 60% plans and prepare a 90% PS&E submittal. Kimley-Horn will address up to one (1) round of reasonable, consolidated City ER comments on the 90% plans and prepare a final PS&E submittal.

## Add Alternate Task 7 – Traffic Signal Modification (Alameda Ave & Emerson St)

This add alternate task consist of the modification of the existing traffic signal at the intersection of Alameda Ave & Emerson St in order to account for the revised lane configuration noted in the Project Understanding. It is understood that the traffic signal modification is anticipated to consist of the removal of the existing traffic signal pole, mast arm, equipment, controller, and curb ramps on the southeast corner and replacement with a new traffic signal pole, mast arm, equipment, ground boxes, controller, ground boxes, and conduit runs.

As of the timing of this draft scope development (9/17/25), scope and fee for this task are still being considered; however, this task is anticipated to consist of the following services:

- Topographic survey;
- Signal design services;
- Civil and curb ramp design;
- Traffic signal interconnect improvements;
- Electrical design and service provider coordination; and
- Drainage modification or analysis is not anticipated or included.

## Additional Services

Any services not specifically provided for in the above scope will be billed as additional services and performed at Kimley-Horn's then-current hourly rates. Additional services Kimley-Horn can provide include, but are not limited to, the following:

- Travel time runs; and
- Re-calibration of traffic model.

DRAFT

## Schedule

Kimley-Horn will perform the services as expeditiously as practicable with the goal of meeting a mutually agreed upon schedule.

- Revised Task 1: Project Management and Meetings – Assumed for project duration, up to nine (9) months
- Revised Task 2: Data Collection – Assumed 1 month
- Revised Task 3: Traffic and Safety Analysis and Evaluation – Assumed 2-3 months
- Revised Task 5: Public Engagement – Assumed 1 month
- Revised Task 6: Final Design – Assumed 4-6 months with portions running concurrently with Revised Task 3

## Fee and Expenses

Kimley-Horn will perform the services described in the new and revised tasks outlined below for the additional labor fee as follows:

| Task | Description | Additional Fee |
|---|---|---|
| Revised Task 1 | Project Management and Meetings | $13,385 |
| Revised Task 2 | Data Collection | $4,955 |
| Revised Task 3 | Traffic and Safety Analysis and Evaluation | $14,540 |
| Revised Task 5 | Public Engagement | $5,705 |
| Revised Task 6 | Final Design | $52,955 |
| | **Total New Amendment #4 Fees** | **$91,540** |
| Add Alternate Task 7 | Traffic Signal Modification (Alameda Ave & Emerson St) | $ TBD |

## Closure

We appreciate the opportunity to provide these services to you and are excited to continue to support the City and County of Denver on this project. Please contact me if you have any questions.

Sincerely,

**KIMLEY-HORN AND ASSOCIATES, INC.**

By: Matt Ciarkowski, P.E.
Project Manager

DRAFT